



SITE PREPARATION RECOMMENDATIONS

Buildings with Pressure-Treated Runners and Wood Floors:

- 4 to 6 inches of road base gravel
- The pad needs to be 1 foot larger than the building on each side and front and back.
- Needs to be completely level

Floorless Buildings (Animal Shelter):

- Make sure ground/dirt/gravel is level.
- If you are choosing a gravel pad, make sure the pad is 1 foot larger than the building on each side and front and back.

Delivery:

- To deliver fully assembled we need 2' more room than the width of the building. Need 16' height. No branches or trees can be in the way.

For best results and for the longevity of your building we recommend a level gravel pad.

Outpouring Space is NOT responsible for any and all site preparation (gravel, concrete, dirt, etc.) and assumes no liability for it. If the pad is out of level and the Customer wants the Building to be level, additional charges will incur.

If anchors need to be installed, you will need to call your 811 dig number to get locates done.